BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
Schedule-B

NAME OF THE WORK: Construction of RCC drain in 14th 15th 16th cross roads at Ravindra Nagara in ward no. 13 in Shettyhalli sub division

Sl. No	Description of work	Unit	Qty	Rate to be Quoted by Contractor K.Jagadish	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specifications and directions of engineer in charge of the work	Cum	527.10	182.03	Rupees One Hundred Eighty Two and Three Paise Only
2	Removing B S Slab Drain And Stacking etc complete as per specifications and directions of engineer in charge of the work	sqm	677.70	67.99	Rupees Sixty Seven and Ninety Nine Paise Only
3	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2 complete as per specifications and directions of engineer in charge of the work **From Using Available coarse aggregates**	Cum	59.80	4596.82	Rupees Four Thousand Five Hundred Ninety Six and Eighty Two Paise Only
4	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2 complete as per specifications and directions of engineer in charge of the work	Cum	15.50	5337.01	Rupees Five Thousand Three Hundred Thirty Seven and One Paise Only

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Division, Bangalore-560057

Scanned by CamScanner

5	Proveding and laying plain reinforced cement concrete for side drains using M 20 nominal mix concrete with OPC cement 360kgs With 20mm and down size ganite metal course aggregates and gobcum and fine aggregates @0.43cum machine mixed,well compacted for walls and bottom including centring,shuttring,cost of materials, HOM of machinaries. Complete Excluding cost of steel asper MORTH Specification no1500,1700,2200. Wall And Bottom thickness 15cm complete as per specifications and directions of engineer in charge of the work	cum	180.72	11413.1	Rupees Eleven Thousand Four Hundred Thirteen and Ten Paise Only
6	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per pecifications.Specification No. KBS 4.6.3, TMT bars Fe 500, complete as per specifications and directions of engineer in charge of the work	Tonne	10.84	66459.82	Rupees Sixty Six Thousand Four Hundred Fifty Nine and Eighty Two Paise Only
7	Providing & laying reinforced cement precast slabs of mix CC 1:1:1/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specifications. and directions of engineer in charge of the work	sqm	373.50	1756.58	Rupees One Thousand Seven Hundred Fifty Six and Fifty Eight Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Scanned by CamScanner